


MINERvA

Tracking Prototype Commissioning

Fermilab All
Experimenters' Meeting




December 22, 2008

Dave Schmitz



MINERvA Overview



- a finely segmented, fully active detector for study of **neutrino-nucleus** interactions in the GeV energy range
- provide crucial information for current and future **oscillation experiments**
- make use of existing intense NuMI beam and MINOS near detector for muon spectrometer
- range of nuclear targets for study of **nuclear effects** in neutrino interactions (He, C, Fe, Pb)



D. Schmitz


Tracking Prototype

- comprehensive test of :
 - detector design
 - component production
 - detector assembly
 - calibration techniques and implementations
 - event reconstruction
- 10 fully active tracking modules
 - 2 scintillator planes @ 17 mm each
- 10 ECAL modules
 - 2 lead sheets @ 2 mm each
 - 2 scintillator planes @ 17 mm each
- 4 HCAL modules
 - 1 steel sheet @ 25 mm
 - 1 scintillator plane @ 17 mm





Modules

- fully active scintillator planes
- triangular geometry allows charge sharing for better position resolution



- Tracking/ECAL modules alternate **U/X** **V/X** ID views
- HCAL modules only one Inner Detector (ID) view (Fe 1" thick)
- Outer Detector (OD) scintillator bars



Tracking Prototype

- currently commissioning in Wideband Hall




Status of TP Construction

- 13 (of 24) modules hanging in Wideband Hall with 12 instrumented as of last Friday
- 14th mapped and ready to hang with 2 more frames welded
- on track to finish commissioning in Feb 09
- excellent collaboration between Universities and the lab
 - many components assembled here (Labs 6,7,G) and at Universities, final full assembly in Wideband
 - lots of effort by student collaborators from US and Latin American institutions


	required for TP	produced and @ FNAL
extruded scintillator bars	5588(ID) + 1152(OD)	all
wavelength shifting fiber	~18 km	all
ID scintillator planes	44	40
OD scintillator assemblies	144	104
steel frame pieces	144	144
2 mm lead sheets ECAL	20	20
25 mm steel sheets HCAL	4	4
PMTs and boxes	105	105
FEBs	105	105

cosmic
trigger panel


10 Tracking + 2 ECAL instrumented
12/19



7 13 modules hanging 12/19




First ECAL Modules – 2 mm Pb sheets



Module and PMT Calibration




- All modules are source mapped in Wideband before being hung
strip position, relative strip response, attenuation along strips



(Jaewon Park, Melanie Day, Bob Bradford, U. of Rochester)




- Light injection system installed for PMT gain calibration




LI


Cosmic muons in TP





- hit doublets
- clustering, tracking algorithms
- PEs per cluster



(Ben Ziemer, UC Irvine)










(B. Ziemer, UC Irvine)


Reconstructing muons

(B. Ziemer, UC Irvine)



Summary

- **MINERvA Tracking Prototype detector** construction more than half complete in Wideband Hall
- Expected completion in Feb '09
- Very successful commissioning so far:
 - construction, mapping, and instrumenting of tracking and ECAL modules
 - DAQ and Light Injection systems
 - first round of calibrations
 - reconstruction software
 - cosmic rays
- Once TP construction complete, next step to move TP underground upstream of the MINOS detector and test response to a neutrino beam



Backups

MINERvA Energy Range

